



The Greater Toronto Area (GTA) Project – HDD and Direct Pipe®	
Location	Toronto, Ontario, Canada
Date Completed	September 2015
Project Type	Gas
Equipment	Mears' Two (2) 140,000 lb. rigs, 1.3 Million lb. rig and 1.1 Million lb. rig
Owner/Client	Enbridge Gas Distribution
Length, Pipe Diameter, Pipe Material	42-inch Steel, Seven (7) Crossings: (HDD) 1266-ft (386-m), 1670-ft (509-m), 1735-ft (529-m), 1765-ft (538-m), 3398-ft (1036-m), 3897-ft (1188-m) (Direct Pipe®) 1427-ft (435-m)
Type of Crossing	Reservoir, Road, Highway, Creek, River
Project Summary	Mears performed a total of seven crossings. Six of the crossings were installed via HDD and one was a Direct Pipe® crossing. The HDD installations were located at the Finch & Claireville Reservoir, Highway 401, Mavis Road, Bramalea Road, Highway 410, and Mississauga Road/Levis Creek and the Direct Pipe® was located at Credit River.

