



	ConocoPhillips Pipeline Re-route
Location	Billings, MT
Date Completed	January 2009
Project Type	Pipeline
Equipment	Mears' 1.1 Million lb. rig
Owner/Client	ConocoPhillips/Pro Pipe Services
Engineer	
Length, Pipe Diameter, Pipe Material	10-inch Steel: 1,633-ft
Type of Crossing	Highway, Road
Project Summary	Pro Pipe Services, Energy Contract Services and Mears Group, Inc. set a high standard in safety, design and planning on a horizontal directional drilling project in Billings, Montana. Contracted by Pro Pipe Services (PPS), Mears installed a 10-inch steel pipeline in the city limits of Billings. The 1,635-foot line replaced the existing product line to make way for a road expansion project at Airport Road. This product line connects to a major oil refinery located in Billings.

